



*previous*

STATE OF FLORIDA  
DEPARTMENT OF HEALTH  
ONSITE SEWAGE TREATMENT AND DISPOSAL  
SYSTEM  
APPLICATION FOR CONSTRUCTION PERMIT

PERMIT NO. 05-310-18  
DATE PAID: 8/15/18  
FEE PAID: 1850  
RECEIPT #: 1/3763366  
AP 1344731

APPLICATION FOR:

☐ New System ☐ Existing System ☐ Holding Tank ☐ Innovative  
☒ Repair ☐ Abandonment ☐ Temporary ☐

APPLICANT: Alachua County Housing Authority

AGENT: New Some Well 3 Septic

TELEPHONE:

MAILING ADDRESS: 12718 NW 77th Ter Alachua, FL 32615

TO BE COMPLETED BY APPLICANT OR APPLICANT'S AUTHORIZED AGENT. SYSTEMS MUST BE CONSTRUCTED BY A PERSON LICENSED PURSUANT TO 489.105(3)(m) OR 489.552, FLORIDA STATUTES. IT IS THE APPLICANT'S RESPONSIBILITY TO PROVIDE DOCUMENTATION OF THE DATE THE LOT WAS CREATED OR PLATTED (MM/DD/YY) IF REQUESTING CONSIDERATION OF STATUTORY GRANDFATHER PROVISIONS.

PROPERTY INFORMATION

LOT: 3 BLOCK: NA SUBDIVISION: Thistle Hills East PLATTED: 6/24/1970 1962

PROPERTY ID #: 64974.003.000 ZONING: R-2 I/M OR EQUIVALENT: ☒ Y ☐ N

PROPERTY SIZE: 1.85 ACRES WATER SUPPLY: PRIVATE PUBLIC ☐ ☒ <=2000GPD ☒ >2000GPD

IS SEWER AVAILABLE AS PER 381.0065, FS? ☒ Y ☐ N DISTANCE TO SEWER: NA

PROPERTY ADDRESS: 13555 SW 156th TER Archer 32618

DIRECTIONS TO PROPERTY: left onto University Ave, left onto SW 11th St, Right onto SW County Road 386, left onto SW 156th Ter, Destination on left.

BUILDING INFORMATION

☒ RESIDENTIAL ☐ COMMERCIAL

Unit No	Type of Establishment	No. of Bedrooms	Building Area Sqft	Commercial/Institutional System Design Table 1, Chapter 64E-6, FAC
1	SFR	4	1304	
2				
3				
4				

☐ Floor/Equipment Drains ☐ Other (Specify)

SIGNATURE:

*Kyle Meyer*

DATE: 5/8/18

ACHD-E22101  
2018 MAY 15 PM 8 33  
A. DENNIS



STATE OF FLORIDA  
DEPARTMENT OF HEALTH  
ONSITE SEWAGE TREATMENT AND DISPOSAL SYSTEM  
EXISTING SYSTEM AND SYSTEM REPAIR EVALUATION

PERMIT # 5-310-18

APPLICANT:

Alachua County Housing Authority

CONTRACTOR / AGENT:

Newson Well & Septic

LOT:

3

BLOCK:

NA

SUBDIV:

Thistle Hills East

ID#:

04974-00

TO BE COMPLETED BY FLORIDA REGISTERED ENGINEER, DEPARTMENT EMPLOYEE, SEPTIC TANK CONTRACTOR OR OTHER CERTIFIED PERSON. SIGN AND SEAL ALL SUBMITTED DOCUMENTS. COMPLETE ALL APPLICABLE ITEMS. COMPLETE TANK CERTIFICATION BELOW OR NOTE IN REMARKS WHY THE TANKS CANNOT BE CERTIFIED.

EXISTING TANK INFORMATION

103" x 48" x 42" = 898.9  
[ 1900 ] GALLONS SEPTIC TANK/GPD ATU LEGEND: N/A MATERIAL: Percod BAFFLED: [ X ]  
[ ] GALLONS SEPTIC TANK/GPD ATU LEGEND: MATERIAL: BAFFLED: [ ]  
[ ] GALLONS GREASE INTERCEPTOR LEGEND: MATERIAL: # PUMPS: [ ]  
[ ] GALLONS DOSING TANK LEGEND: MATERIAL: # PUMPS: [ ]

I CERTIFY THAT THE LISTED TANKS WERE PUMPED ON 4/12/17 BY Phil Meyer.  
THE VOLUMES SPECIFIED AS DETERMINED BY [ DIMENSIONS / FILLING / LEGEND ], ARE FREE OF OBSERVABLE DEFECTS OR LEAKS, AND HAVE A [ SOLIDS DEFLECTION DEVICE / OUTLET FILTER DEVICE ] INSTALLED.

SIGNATURE OF LICENSED CONTRACTOR

BUSINESS NAME

DATE

EXISTING DRAINFIELD INFORMATION

[ 144 ] SQUARE FEET PRIMARY DRAINFIELD SYSTEM NO. OF TRENCHES [ 1 ] DIMENSIONS: 6 x 24  
[ ] SQUARE FEET SYSTEM NO. OF TRENCHES [ ] DIMENSIONS: x  
TYPE OF SYSTEM: [ X ] STANDARD [ ] FILLED [ ] MOUND [ ] Rock  
CONFIGURATION: [ ] TRENCH [ X ] BED [ ]  
DESIGN: [ ] HEADER [ X ] D-BOX [ X ] GRAVITY SYSTEM [ ] DOSED SYSTEM  
ELEVATION OF BOTTOM OF DRAINFIELD IN RELATION TO EXISTING GRADE 38 INCHES [ ABOVE ] [ BE ]

SYSTEM FAILURE AND REPAIR INFORMATION

[ 1967 ] SYSTEM INSTALLATION DATE TYPE OF WASTE [ X ] DOMESTIC [ ] COMMERCIAL  
[ 400 ] GPD ESTIMATED SEWAGE FLOW BASED ON [ ] METERED WATER [ X ] TABLE 1, 64E-6,

SITE [ ] DRAINAGE STRUCTURES [ ] POOL [ ] PATIO / DECK [ ] PARKING  
CONDITIONS: [ ] SLOPING PROPERTY [ ]

NATURE OF [ ] HYDRAULIC OVERLOAD [ ] SOILS [ X ] MAINTENANCE [ ] SYSTEM DAMAGE  
FAILURE: [ ] DRAINAGE / RUN OFF [ ] ROOTS [ ] WATER TABLE [ X ] Age

FAILURE [ ] SEWAGE ON GROUND [ ] TANK [ ] D BOX/HEADER [ ] DRAINFIELD  
SYMPTOM: [ X ] PLUMBING BACKUP [ ]

REMARKS/ADDITIONAL CRITERIA

Replace to Repair Standards

SUBMITTED BY:

TITLE/LICENSE CEHP

DATE: 5/8/17

DA 4015, 08/09 (Obsoletes previous editions which may not be used)

Incorporated 64E-6.001, FAC



STATE OF FLORIDA  
DEPARTMENT OF HEALTH  
ONSITE SEWAGE TREATMENT AND DISPOSAL SYSTEM  
SITE EVALUATION AND SYSTEM SPECIFICATIONS

PERMIT #. 05-310-18

APPLICANT: Alachua County Housing Authority AGENT: Newsome well + septic

LOT: 3 BLOCK: NA SUBDIVISION: Thistle Hills East.

PROPERTY ID #: 04924-003-000 [Section/Township/Parcel No. or Tax ID Number]

13555 SW 156th Ter Archer Fl 32618

TO BE COMPLETED BY ENGINEER, HEALTH DEPARTMENT EMPLOYEE, OR OTHER QUALIFIED PERSON. ENGINEERS MUST PROVIDE REGISTRATION NUMBER AND SIGN AND SEAL EACH PAGE OF SUBMITTAL. COMPLETE ALL ITEMS.

PROPERTY SIZE CONFORMS TO SITE PLAN: ☒ YES ☐ NO NET USABLE AREA AVAILABLE: 185 ACRES  
TOTAL ESTIMATED SEWAGE FLOW: 400 GALLONS PER DAY [RESIDENCES-TABLE 1/OTHER-TABLE 2]  
AUTHORIZED SEWAGE FLOW: 462.5 GALLONS PER DAY [1500 GPD/ACRE OR 2500 GPD/ACRE]  
UNOBSTRUCTED AREA AVAILABLE: 10000 SQFT UNOBSTRUCTED AREA REQUIRED: 600 SQFT

BENCHMARK/REFERENCE POINT LOCATION: orange 4th on A/C Road  
ELEVATION OF PROPOSED SYSTEM SITE IS 2 [INCHES/FT] [ABOVE/BELOW] BENCHMARK/REFERENCE POINT

THE MINIMUM SETBACK WHICH CAN BE MAINTAINED FROM THE PROPOSED SYSTEM TO THE FOLLOWING FEATURES  
SURFACE WATER: NA FT DITCHES/SWALES: NA FT NORMALLY WET? ☐ YES ☒ NO  
WELLS: PUBLIC: NA FT LIMITED USE: NA FT PRIVATE: NA FT NON-POTABLE: NA FT  
BUILDING FOUNDATIONS: 6 FT PROPERTY LINES: 6 FT POTABLE WATER LINES: 32 FT

SITE SUBJECT TO FREQUENT FLOODING: ☐ YES ☒ NO 10 YEAR FLOODING? ☐ YES ☒ NO  
10 YEAR FLOOD ELEVATION FOR SITE: NA FT MSL/NGVD SITE ELEVATION: NA FT MSL/NGVD

SOIL PROFILE INFORMATION SITE 1

2" Above RP

MUNSELL #/COLOR	TEXTURE	DEPTH
10YR 4/2	FS	0 TO 7
10YR 5/4 4/4	FS	7 TO 20
10YR 6/4, 5/6 2.5YR 5/6	FS	20 TO 48
10YR 7/4 8/2, 2.5YR 5/6 5/8	FS	48 TO 62
2.5YR 5/6, 5/8 10YR 6/4	LS	62 TO 72
		TO
		TO
		TO
		TO

USDA SOIL SERIES: Mapped Arredondo

SOIL PROFILE INFORMATION SITE 2

10" Below RP

MUNSELL #/COLOR	TEXTURE	DEPTH
10YR 4/2	FS	0 TO 6
10YR 4/2, 5/4	FS	6 TO 16
10YR 6/4, 5/6	FS	16 TO 48
10YR 7/4, 8/2 2.5YR 5/6 5/8	FS	48 TO 63
2.5YR 5/6, 5/8 10YR 6/4	LS	63 TO 72
		TO
		TO
		TO
		TO

USDA SOIL SERIES: Mapped Arredondo

OBSERVED WATER TABLE: 72 INCHES [ABOVE / BELOW] EXISTING GRADE. TYPE: [PERCHED / APPARENT]  
ESTIMATED WET SEASON WATER TABLE ELEVATION: 72 INCHES [ABOVE / BELOW] EXISTING GRADE  
HIGH WATER TABLE VEGETATION: ☐ YES ☒ NO MOTTLING: ☒ YES ☐ NO DEPTH: 20 INCHES

SOIL TEXTURE/LOADING RATE FOR SYSTEM SIZING: FS Table VII DEPTH OF EXCAVATION: 0.10 INCHES  
DRAINFIELD CONFIGURATION: ☐ TRENCH ☒ BED ☐ OTHER (SPECIFY)

REMARKS/ADDITIONAL CRITERIA: Remove old drainfield. Replace to repair structure

\* per John Mayfield email 5/13/18

SITE EVALUATED BY: CEHP 17-1159

DATE: 5/8/18



STATE OF FLORIDA  
DEPARTMENT OF HEALTH  
ONSITE SEWAGE TREATMENT AND DISPOSAL  
SYSTEM

5-310-18  
PERMIT #: 01-SA-1847446  
APPLICATION #: AP1344734  
DATE PAID: \_\_\_\_\_  
FEE PAID: \_\_\_\_\_  
RECEIPT #: \_\_\_\_\_  
DOCUMENT #: PR1119416

CONSTRUCTION PERMIT FOR: OSTDS Repair  
APPLICANT: (Alachua County Housing Authority Lot 3)  
PROPERTY ADDRESS: 13555 SW 156th Ter Archer, FL 32618  
LOT: 3 BLOCK: NA SUBDIVISION: Thistle Hills East  
PROPERTY ID #: 04974-003-000 [SECTION, TOWNSHIP, RANGE, PARCEL NUMBER]  
[OR TAX ID NUMBER]

SYSTEM MUST BE CONSTRUCTED IN ACCORDANCE WITH SPECIFICATIONS AND STANDARDS OF SECTION 381.0065, F.S., AND CHAPTER 64E-6, F.A.C. DEPARTMENT APPROVAL OF SYSTEM DOES NOT GUARANTEE SATISFACTORY PERFORMANCE FOR ANY SPECIFIC PERIOD OF TIME. ANY CHANGE IN MATERIAL FACTS, WHICH SERVED AS A BASIS FOR ISSUANCE OF THIS PERMIT, REQUIRE THE APPLICANT TO MODIFY THE PERMIT APPLICATION. SUCH MODIFICATIONS MAY RESULT IN THIS PERMIT BEING MADE NULL AND VOID. ISSUANCE OF THIS PERMIT DOES NOT EXEMPT THE APPLICANT FROM COMPLIANCE WITH OTHER FEDERAL, STATE, OR LOCAL PERMITTING REQUIRED FOR DEVELOPMENT OF THIS PROPERTY.

SYSTEM DESIGN AND SPECIFICATIONS

T [ 898 ] GALLONS / GPD Ex Septic CAPACITY  
A [ 0 ] GALLONS / GPD CAPACITY  
N [ 0 ] GALLONS GREASE INTERCEPTOR CAPACITY [MAXIMUM CAPACITY SINGLE TANK:1250 GALLONS]  
K [     ] GALLONS DOSING TANK CAPACITY [ ] GALLONS @ [ ] DOSES PER 24 HRS #Pumps [ ]  
D [ 400 ] SQUARE FEET Drainfield Replacement SYSTEM  
R [ 0 ] SQUARE FEET SYSTEM  
A TYPE SYSTEM: [x] STANDARD [ ] FILLED [ ] MOUND [ ]  
I CONFIGURATION: [ ] TRENCH [x] BED [ ]  
N  
F LOCATION OF BENCHMARK: orange dot on AC Pad  
I ELEVATION OF PROPOSED SYSTEM SITE [ 2.00 ] [ INCHES / FT ] [ ABOVE / BELOW ] BENCHMARK/REFERENCE POINT  
E BOTTOM OF DRAINFIELD TO BE [ 36.00 ] [ INCHES / FT ] [ ABOVE / BELOW ] BENCHMARK/REFERENCE POINT  
L  
D FILL REQUIRED: [ 0.00 ] INCHES EXCAVATION REQUIRED: [ ] INCHES

O The system is sized for 4 bedrooms with a maximum occupancy of 8 persons (2 per bedroom), for a total estimated flow of 400 gpd. Required drainfield area based on rule 64E-6.015(6)(c)2. Remove existing drainfield from proposed drainfield area and properly dispose with spoils. Install approved bed design per rule or manufactures instruction whichever is greater.  
T Private site evaluation shall be confirmed at time of installation inspection. ACHD encourages 667 ft2 for new sizing  
H standards in proposed configuration.  
E  
R

SPECIFICATIONS BY: John Mayfield TITLE: CEHP  
APPROVED BY: Tom S Harris TITLE: Assistant EH Director Alachua CHD  
DATE ISSUED: 05/31/2018 EXPIRATION DATE: 08/29/2018  
DH 4016, 08/09 (Obsoletes all previous editions which may not be used)  
Incorporated: 64E-6.003, FAC

### NOTICE OF RIGHTS

A party whose substantial interest is affected by this order may petition for an administrative hearing pursuant to sections 120.569 and 120.57, Florida Statutes. Such proceedings are governed by Rule 28-106, Florida Administrative Code. A petition for administrative hearing must be in writing and must be received by the Agency Clerk for the Department, within twenty-one (21) days from the receipt of this order. The address of the Agency Clerk is 4052 Bald Cypress Way, BIN A-02, Tallahassee, Florida 32399. The Agency Clerk's facsimile number is 850-413-8743.


Mediation is not available as an alternative remedy.

Your failure to submit a petition for hearing within 21 days from receipt of this order will constitute a waiver of your right to an administrative hearing, and this order shall become a 'final order'.

Should this order become a final order, a party who is adversely affected by it is entitled to judicial review pursuant to Section 120.68, Florida Statutes. Review proceedings are governed by the Florida Rules of Appellate Procedure. Such proceedings may be commenced by filing one copy of a Notice of Appeal with the Agency Clerk of the Department of Health and a second copy, accompanied by the filing fees required by law, with the Court of Appeal in the appropriate District Court. The notice must be filed within 30 days of rendition of the final order.


05-310-18

13555 SW 156<sup>th</sup> Ter.  
Archer, FL 32618



*Any*  
5/8/18

NOT TO SCALE  $\rightarrow$



↑ N

45-310-18





By John F. Kelly, Deputy Clerk

## Harris, Todd S

---

**From:** John Mayfield <flsepticsolutions@yahoo.com>  
**Sent:** Wednesday, May 23, 2018 7:15 PM  
**To:** Harris, Todd S  
**Subject:** Re: Alachua County Housing Authority 05-310-18

Just a polychromatic matrix. Not redoximorphic feature.  
If you need anything else please let me know.

Thank you  
John Mayfield  
Florida Septic Solutions L.L.C.  
386-559-7540

Sent from Yahoo Mail for iPad

On Wednesday, May 23, 2018, 7:10 PM, Harris, Todd S <[Todd.Harris@flhealth.gov](mailto:Todd.Harris@flhealth.gov)> wrote:

Good evening John,

Can you please clarify the 20" mottling depth listed on the attached site evaluation for 13555 SW 156<sup>th</sup> Ter.? If the mottling is associated with a water table please describe the mottles in the soil profiles in contrast and prevalence; otherwise this may need to be revised on the form as this field is specifically for high chroma indicators indicative of wetness. Guess we just need clarification if the profiles are indicative of a polychromatic matrix or if it is high chroma redoximorphic features.

Thank you,

Todd Harris  
Environmental Manager  
Florida Department of Health in Alachua County  
224 SE 24th St.  
Gainesville, FL 32641  
Office [352-334-7932](tel:352-334-7932)  
Fax [352-334-7935](tel:352-334-7935)

Please note: Florida has a very broad public records law. Most written communications to or from state officials regarding state business are public records available to the public and media upon request. Your e-mail communications may therefore be subject to public disclosure



## Property Search Results

The data displayed is the most current data available to the Property Appraiser.

Search Date: 5/15/2018 at 8:26:45 AM

Printer Friendly Page

Parcel: 04974-003-000 GIS Map

<b>Taxpayer:</b>	ALACHUA COUNTY HOUSING, AUTHOR	<b>Legal:</b> THISTLE HILLS EAST PB H-27 LOT 3 OR 804/350
<b>Mailing:</b>	701 NE 1ST ST GAINESVILLE, FL 32601	
<b>9-1-1 Address:</b>	13555 SW 156TH TER ARCHER	
<b>Sec-Twn-Rng:</b>	16-11-18	
<b>Property Use:</b>	08600 - Cty Inc Nonmuni	
<b>Tax Jurisdiction:</b>	Archer 2700	
<b>Area:</b>	City of Archer	
<b>Subdivision:</b>	Thistle Hills East	


	Property	Land	Land	Building	Misc	Total	Deferred	County	School	County	School	County	School
Year	Use	Value	Just Value	Value	Value	Just Value	Value	Assessed	Assessed	Exempt	Exempt	Taxable	Taxable
2017	Cty Inc Nonmuni	16000	16000	47300	100	63400	0	63400	63400	63400	63400	0	0
2016	Cty Inc Nonmuni	16000	16000	44300	100	60400	0	60400	60400	60400	60400	0	0
2015	Cty Inc Nonmuni	16000	16000	45200	100	61300	0	61300	61300	61300	61300	0	0
2014	Cty Inc Nonmuni	16000	16000	45400	100	61500	0	61500	61500	61500	61500	0	0
2013	Cty Inc Nonmuni	16000	16000	46300	100	62400	0	62400	62400	62400	62400	0	0
2012	Cty Inc Nonmuni	16000	16000	47200	100	63300	0	63300	63300	63300	63300	0	0
2011	Cty Inc Nonmuni	16000	16000	49900	100	66000	0	66000	66000	66000	66000	0	0
2010	Cty Inc Nonmuni	16000	16000	52700	100	68800	0	68800	68800	68800	68800	0	0
2009	Cty Inc Nonmuni	16000	16000	57100	100	73200	0	73200	73200	73200	73200	0	0
2008	Single Family	16000	16000	63400	100	79500	0	79500	0	79500	0	0	0

## Land

Use	Zoning Type	Zoning Desc	Unit Type	Units
SFR	R-2		Unit	1

## Building

<b>Actual Year Built</b>	1967
<b>Effective Year Built</b>	1967
<b>Building Quality</b>	Average
<b>Building Style</b>	01
<b>Building Use</b>	0100 - Single Family
<b>Bedrooms</b>	4
<b>Baths</b>	1.5
<b>Stories</b>	1.0
<b>Exterior Wall 1</b>	Concrete Block
<b>Exterior Wall 2</b>	N/A
<b>Interior Wall 1</b>	Drywall
<b>Interior Wall 2</b>	N/A
<b>Floor Cover 1</b>	Cork Tile
<b>Floor Cover 2</b>	N/A
<b>Roof Cover</b>	Asphalt
<b>Roof Structure</b>	Gable/Hip
<b>AC</b>	Central
<b>Heating Type</b>	Forced Air
<b>Heating System</b>	Electric
<b>Total Square Feet</b>	1304
<b>Heated Square Feet</b>	1224
<b>Area Type</b>	<b>Square Footage</b>
BAS (BASE AREA)	1224



## Miscellaneous

Description	Unit Type	Units
4680 - Paving 1	SF	250

[Link to TaxCollector Record](#)

The information that is supplied by the Alachua County Property Appraiser's office is public information data and must be accepted and used with the understanding that the data was collected primarily for the use and purpose of creating a Property Tax Roll per Florida Statute. The Alachua County Property Appraiser's Office will not be held liable as to the validity, correctness, accuracy, completeness, and / or reliability of this data. The Alachua County Property Appraiser's Office furthermore assumes no liability whatsoever associated with the use or misuse of this public information data.

Alachua County Property Appraiser • 515 N Main Street Suite 200 • Gainesville, FL 32601 • 352-374-5230 (FAX) 352-374-5278



STATE OF FLORIDA  
DEPARTMENT OF HEALTH  
ONSITE SEWAGE TREATMENT AND DISPOSAL SYSTEM  
CONSTRUCTION INSPECTION AND FINAL APPROVAL

APPLICATION #: AP1344734

PERMIT #: 01-SA-1847446

DOCUMENT #: F11240607

DATE PAID: 05/15/2018

FEE PAID: 185.00

RECEIPT #: 1-PID-3544867

APPLICANT: Alachua County Housing Authority Lot 3

AGENT: Newsome Well and Septic

PROPERTY ADDRESS: 13555 SW 156th Ter Archer, FL 32618

LOT: 3

BLOCK:

SUBDIVISION: Thistle Hills East

ID#: 04974-003-000

CHECKED [X] ITEMS ARE NOT IN COMPLIANCE WITH STATUTE OR RULE AND MUST BE CORRECTED.

TANK INSTALLATION

[ ] [01] TANK SIZE [1] 898.00 <sup>EX</sup> [2] -  
[ ] [02] TANK MATERIAL Concrete  
[ ] [03] OUTLET DEVICE SD  
[ ] [04] MULTI-CHAMBERED [ ] Y [ ] N  
[ ] [05] OUTLET FILTER -  
[ ] [06] LEGEND 1. Unknown 2. -  
[ ] [07] WATERTIGHT  
[ ] [08] LEVEL  
[ ] [09] DEPTH TO LID

DRAINFIELD INSTALLATION

[ ] [10] AREA [1] 405 [2] - SQFT  
[ ] [11] DISTRIBUTION BOX - HEADER X  
[ ] [12] NUMBER OF DRAINLINES 1. 5.00 2. -  
[ ] [13] DRAINLINE SEPARATION  
[ ] [14] DRAINLINE SLOPE  
[ ] [15] DEPTH OF COVER  
[ ] [16] ELEVATION [ ] ABOVE [ ] BELOW 1BM 36.00  
[ ] [17] SYSTEM LOCATION ⊙  
[ ] [18] DOSING PUMPS  
[ ] [19] AGGREGATE SIZE  
[ ] [20] AGGREGATE EXCESSIVE FINES  
[ ] [21] AGGREGATE DEPTH

FILL / EXCAVATION MATERIAL

[ ] [22] FILL AMOUNT  
[ ] [23] FILL TEXTURE  
[ ] [24] EXCAVATION DEPTH  
[ ] [25] AREA REPLACED  
[ ] [26] REPLACEMENT MATERIAL

SETBACKS

[ ] [27] SURFACE WATER 11 FT  
[ ] [28] DITCHES 11 FT  
[ ] [29] PRIVATE WELLS 11 FT  
[ ] [30] PUBLIC WELLS 11 FT  
[ ] [31] IRRIGATION WELLS 11 FT  
[ ] [32] POTABLE WATER 31 FT  
[ ] [33] BUILDING FOUNDATIONS 5 FT  
[ ] [34] PROPERTY LINES 5 FT  
[ ] [35] OTHER 11 FT

FILLED / MOUND SYSTEM

[ ] [36] DRAINFIELD COVER  
[ ] [37] SHOULDERS  
[ ] [38] SLOPES  
[ ] [39] STABILIZATION -

ADDITIONAL INFORMATION

[ ] [40] UNOBSTRUCTED AREA  
[ ] [41] STORMWATER RUNOFF  
[ ] [42] ALARMS  
[ ] [43] MAINTENANCE AGREEMENT  
[ ] [44] BUILDING AREA  
[ ] [45] LOCATION CONFORMS WITH SITE PLAN  
[ ] [46] FINAL SITE GRADING  
[ ] [47] CONTRACTOR Kyle Myers (Newsome Well &  
[ ] [48] OTHER 27 # ADS ARC 24 w/cloth  
As Bed

ABANDONMENT

[ ] [49] TANK PUMPED 06/05/2018  
[ ] [50] TANK CRUSHED & FILLED 06/05/2018

Comments: Comments are on page 2.

Soils ok

CONSTRUCTION [ ] APPROVED / DISAPPROVED [ ] Fred L. Bennett Alachua CHD DATE: 06/05/2018  
Environmental Specialist II Fred L. Bennett (Department of Health in Al

FINAL SYSTEM [ ] APPROVED / DISAPPROVED [ ] Fred L. Bennett Alachua CHD DATE: 06/05/2018  
Environmental Specialist II Fred L. Bennett (Department of Health in Al

(Explanation of Violations on following page)

DH 4016, 08/09 (Obsoletes all previous editions which may not be used)

Incorporated: 64E-6.003, FAC


EH Database v 1.0.1

AP1344734

EID1847446

Page 2 of 3

on



STATE OF FLORIDA  
DEPARTMENT OF HEALTH  
ONSITE SEWAGE TREATMENT AND DISPOSAL SYSTEM  
CONSTRUCTION INSPECTION AND FINAL APPROVAL

APPLICATION #: AP1344734  
PERMIT #: 01-SA-1847446  
DOCUMENT #: F11240607  
DATE PAID: 05/15/2018  
FEE PAID: 185.00  
RECEIPT #: 1-PID-3544867

Violation Number	Comment

Comments

Existing tank information per DH4015 page 4. second tank in failure pointed out by Tenant see as built second tank abandoned and sewer plumbed to joined system

DH 4016, 08/09 (Obsoletes all previous editions which may not be used)

Incorporated: 64E-6.003, FAC

EH Database v 1.0.1

AP1344734

EID1847446

6/4/18  
2:46



Kyle  
Newcome

STATE OF FLORIDA  
DEPARTMENT OF HEALTH  
ONSITE SEWAGE TREATMENT AND DISPOSAL SYSTEM  
CONSTRUCTION INSPECTION AND FINAL APPROVAL

6/5/18 Jrees  
@ 2:00

PERMIT NO. 5-310-18  
DATE PAID: 5/15/18  
FEE PAID: 185.00  
RECEIPT #: 13763366  
AP1344734

APPLICANT: Alachua County Housing Authority

AGENT: \_\_\_\_\_

PROPERTY ADDRESS: 13555 SW 15th Terrace, Archer, FL 32618

LOT: \_\_\_\_\_ BLOCK: 3 SUBDIVISION: Thistle Hills East PROPERTY ID #: 04974003-000

CHECKED [X] ITEMS ARE NOT IN COMPLIANCE WITH STATUTE OR RULE AND MUST BE CORRECTED.

TANK INSTALLATION

- [ ] [01] TANK SIZE [1] 900 [2] \_\_\_\_\_  
[ ] [02] TANK MATERIAL concrete  
[ ] [03] OUTLET DEVICE tee  
[ ] [04] MULTI-CHAMBERED [ Y / (N) ]  
[ ] [05] OUTLET FILTER \_\_\_\_\_  
[ ] [06] LEGEND unlc  
[ ] [07] WATERTIGHT \_\_\_\_\_  
[ ] [08] LEVEL \_\_\_\_\_  
[ ] [09] DEPTH TO LID \_\_\_\_\_

2x6+3x5

DRAINFIELD INSTALLATION

- [ ] [10] AREA [1] 405 [2] \_\_\_\_\_ SQFT  
[ ] [11] DISTRIBUTION BOX \_\_\_\_\_ HEADER ✓  
[ ] [12] NUMBER OF DRAINLINES #5  
[ ] [13] DRAINLINE SEPARATION \_\_\_\_\_  
[ ] [14] DRAINLINE SLOPE \_\_\_\_\_  
[ ] [15] DEPTH OF COVER \_\_\_\_\_  
[ ] [16] ELEVATION [ABOVE/BELOW] BM 36  
[ ] [17] SYSTEM LOCATION \_\_\_\_\_  
[ ] [18] DOSING PUMPS \_\_\_\_\_  
[ ] [19] AGGREGATE SIZE \_\_\_\_\_  
[ ] [20] AGGREGATE EXCESSIVE FINES \_\_\_\_\_  
[ ] [21] AGGREGATE DEPTH \_\_\_\_\_

FILL / EXCAVATION MATERIAL

- [ ] [22] FILL AMOUNT \_\_\_\_\_  
[ ] [23] FILL TEXTURE \_\_\_\_\_  
[ ] [24] EXCAVATION DEPTH \_\_\_\_\_  
[ ] [25] AREA REPLACED \_\_\_\_\_  
[X] [26] REPLACEMENT MATERIAL \_\_\_\_\_

SETBACKS

- [ ] [27] SURFACE WATER \_\_\_\_\_ FT  
[ ] [28] DITCHES \_\_\_\_\_ FT  
[ ] [29] PRIVATE WELLS \_\_\_\_\_ FT  
[ ] [30] PUBLIC WELLS \_\_\_\_\_ FT  
[ ] [31] IRRIGATION WELLS \_\_\_\_\_ FT  
[ ] [32] POTABLE WATER LINES 31 FT  
[ ] [33] BUILDING FOUNDATION 5 FT  
[ ] [34] PROPERTY LINES 5 FT  
[ ] [35] OTHER \_\_\_\_\_ FT

FILLED / MOUND SYSTEM

- [ ] [36] DRAINFIELD COVER \_\_\_\_\_  
[ ] [37] SHOULDERS \_\_\_\_\_  
[ ] [38] SLOPES \_\_\_\_\_  
[ ] [39] STABILIZATION \_\_\_\_\_

ADDITIONAL INFORMATION

- [ ] [40] UNOBSTRUCTED AREA \_\_\_\_\_  
[ ] [41] STORMWATER RUNOFF \_\_\_\_\_  
[ ] [42] ALARMS \_\_\_\_\_  
[ ] [43] MAINTENANCE AGREEMENT \_\_\_\_\_  
[ ] [44] BUILDING AREA \_\_\_\_\_  
[ ] [45] LOCATION CONFORMS WITH SITE PLAN \_\_\_\_\_  
[ ] [46] FINAL SITE GRADING \_\_\_\_\_  
[ ] [47] CONTRACTOR Newcome  
[ ] [48] OTHER 27 Arc. 24 w/cloth as bcd

ABANDONMENT

- [ ] [49] TANK PUMPED 6/5/18  
[ ] [50] TANK CRUSHED & FILLED 0/5/18

EXPLANATION OF VIOLATIONS / REMARKS:

- [ ] soils ok  
[ ] Second tank found failing  
[ ] Pumped crushed & Filled Second tank  
[ ] \_\_\_\_\_

CONSTRUCTION ~~APPROVED~~ / DISAPPROVED: David Bennett Alachua CHD DATE: 6-5-18

FINAL SYSTEM ~~APPROVED~~ / DISAPPROVED: David Bennett Alachua CHD DATE: 6-5-18

DH 4016, 08/09 (Obsoletes all previous editions which may not be used)

Incorporated: 64E-6.003, FAC

approved 6-5-18

EMAILED

PERMIT NUMBER:

APPLICANT:

AGENT:

MAILING ADDRESS:

LOT, BLOCK, SUBDIVISION

PROPERTY ID#:

Permit tracking number assigned by CHD.

Property owner's full name.

Property owner's legally authorized representative.

P.O. box or street mailing address for applicant or agent.

Lot, Block and Subdivision for lot or

27 character number for property. (property appraiser ID # or GIS location)

COUNTY HEALTH DEPARTMENT CHECKS (X) ITEMS NOT IN COMPLIANCE WITH CONSTRUCTION PERMIT AND STATUTE OR RULE. INFORMATION IS COMPLETED BY CHD ON FOLLOWING ITEMS:

TANK MATERIAL (concrete, fiberglass, etc)

OUTLET FILTER (manufacturer, make, model)

LEGEND (manufacturer code)

DRAINFIELD AREA (square feet)

DISTRIBUTION BOX / HEADER (check box)

NUMBER OF DRAINLINES (number installed)

SYSTEM ELEVATION (in relation to BM)

DOSING PUMPS (number installed)

SETBACKS (record actual setbacks in ft)

SETBACKS OTHER (as required)

STABILIZATION (date stabilized)

CONTRACTOR (contractor installing system)

ADDITIONAL INFORMATION (as required)

ABANDONMENT TANK PUMPED (date)

TANK CRUSHED AND FILLED (date)

AS BUILT INSTALLATION SKETCH

### EXPLANATION OF VIOLATIONS:

Record item number, explanation of violation, and required corrective action.  
Circle approved or disapproved, CHD signature and date.  
Circle approved or disapproved, CHD signature and date of approval.  
Final approval shall not be granted until the CHD has confirmed that building construction and lot grading are in substantial compliance with plans and specifications submitted with the permit application.

### CONSTRUCTION APPROVAL:

### FINAL APPROVAL:

### ELEVATION WORKSHEET

ELEVATION OF BENCHMARK OR REFERENCE POINT:

EXISTING GROUND

TOP OF AGGREGATE

ELEVATION

[+] SHOT

H.I.

[-] SHOT

H.I.

[-] SHOT

H.I.

[-] SHOT

