

09-743-94 R North land
12-759-91 R South land



STATE OF FLORIDA
DEPARTMENT OF HEALTH
ON-SITE SEWAGE TREATMENT AND DISPOSAL
SYSTEM
APPLICATION FOR CONSTRUCTION PERMIT

PERMIT NO. 10-579-20
DATE PAID: 10/8/20
FEE PAID: 300.00
RECEIPT #: 15048985
AP 1583228

APPLICATION FOR:

☐ New System ☐ Existing System ☐ Holding Tank ☐ Innovative
☒ Repair ☐ Abandonment ☐ Temporary

APPLICANT:

Alachua County Housing Authority

AGENT: Beltz Liquid Waste Management & Portable Toilets, Inc.

TELEPHONE: 352-372-7448

MAILING ADDRESS: 14260 W Newberry Rd, #344, Newberry, FL 32669

TO BE COMPLETED BY APPLICANT OR APPLICANT'S AUTHORIZED AGENT. SYSTEMS MUST BE CONSTRUCTED BY A PERSON LICENSED PURSUANT TO 489.105(3)(a) OR 489.552, FLORIDA STATUTES. IT IS THE APPLICANT'S RESPONSIBILITY TO PROVIDE DOCUMENTATION OF THE DATE THE LOT WAS CREATED OR PLATTED (MM/DD/YY) IF REQUESTING CONSIDERATION OF STATUTORY GRANDFATHER PROVISIONS.

PROPERTY INFORMATION

LOT: 4 BLOCK: SUBDIVISION: Thicket Hills West PLATTED: 1971

PROPERTY ID #: 05081-004-000 ZONING: Res I/M OR EQUIVALENT: (Y/N)

PROPERTY SIZE: 0.17 ACRES WATER SUPPLY: ☐ PRIVATE PUBLIC ☒ <=2000GPD ☒ >2000GPD

IS SEWER AVAILABLE AS PER 381.0065, FS? (Y/N) DISTANCE TO SEWER: FT

PROPERTY ADDRESS: 17056 SW 141st Place, Archer, FL 32618

DIRECTIONS TO PROPERTY: Take SW 170th Street South out of Archer, turn right on SW 141st Pl, go to house on right

BUILDING INFORMATION

☒ RESIDENTIAL

☐ COMMERCIAL

Unit No	Type of Establishment	No. of Bedrooms	Building Area Sqft	Commercial/Institutional System Design Table 1, Chapter 64E-5, FAC
1	1967 SFD	4	1225	
2				
3				
4				

☐ Floor/Equipment Drains ☐ Other (Specify)

SIGNATURE:

[Signature]

DATE:

10/7/2020



STATE OF FLORIDA
DEPARTMENT OF HEALTH
ONSITE SEWAGE TREATMENT AND DISPOSAL SYSTEM
EXISTING SYSTEM AND SYSTEM REPAIR EVALUATION

PERMIT # 1057920

APPLICANT: Alachua County Housing Authority 17056 SW 14th Pl, Gainesville, FL

CONTRACTOR / AGENT: Beltz Liquid Waste Management & Portable Toilets, Inc.

LOT: 4 BLOCK: _____ SUBDIV: Twistle Hills West ID# 05081-004-000

TO BE COMPLETED BY FLORIDA REGISTERED ENGINEER, DEPARTMENT EMPLOYEE, SEPTIC TANK CONTRACTOR OR OTHER CERTIFIED PERSON. SIGN AND SEAL ALL SUBMITTED DOCUMENTS. COMPLETE ALL APPLICABLE ITEMS. COMPLETE TANK CERTIFICATION BELOW OR NOTE IN REMARKS WHY THE TANKS CANNOT BE CERTIFIED.

EXISTING TANK INFORMATION Both: 102" x 36" x 48"

<input checked="" type="checkbox"/> 750	GALLONS SEPTIC TANK / GPD ATU	LEGEND: <u>unknown</u>	MATERIAL: <u>precast</u>	BAFFLED: <input checked="" type="checkbox"/> Y <input type="checkbox"/> N
<input checked="" type="checkbox"/> 750	GALLONS SEPTIC TANK / GPD ATU	LEGEND: _____	MATERIAL: _____	BAFFLED: <input type="checkbox"/> Y <input type="checkbox"/> N
<input type="checkbox"/>	GALLONS GREASE INTERCEPTOR	LEGEND: _____	MATERIAL: _____	
<input type="checkbox"/>	GALLONS DOSING TANK	LEGEND: _____	MATERIAL: _____	# PUMPS: <input type="checkbox"/>

I CERTIFY THAT THE LISTED TANKS WERE PUMPED ON 9/15/20 BY Beltz Liquid Waste Mgmt & PT, HAVE THE VOLUMES SPECIFIED AS DETERMINED BY DIMENSIONS / FILLING / LEGEND, ARE FREE OF OBSERVABLE DEFECTS OR LEAKS, AND HAVE A SOLIDS DEFLECTION DEVICE / OUTLET FILTER DEVICE ☒ INSTALLED.
SIGNATURE OF LICENSED CONTRACTOR [Signature] BUSINESS NAME Beltz Liquid Waste Management & Portable Toilets DATE 10/7/2020

EXISTING DRAINFIELD INFORMATION

☒ 250 SQUARE FEET PRIMARY DRAINFIELD SYSTEM NO. OF TRENCHES ☐ DIMENSIONS: 9 x 28
☐ SQUARE FEET _____ SYSTEM NO. OF TRENCHES ☐ DIMENSIONS: _____
TYPE OF SYSTEM: ☒ STANDARD ☐ FILLED ☐ MOUND ☐
CONFIGURATION: ☐ TRENCH ☒ BED ☐
DESIGN: ☐ HEADER ☒ D-BOX ☐ GRAVITY SYSTEM ☐ DOSED SYSTEM
ELEVATION OF BOTTOM OF DRAINFIELD IN RELATION TO EXISTING GRADE 30 INCHES ☒ ABOVE ☐ BELOW

SYSTEM FAILURE AND REPAIR INFORMATION

☒ 67 SYSTEM INSTALLATION DATE
☒ 400 GPD ESTIMATED SEWAGE FLOW BASED ON _____ TYPE OF WASTE ☐ DOMESTIC ☐ COMMERCIAL
☐ METERED WATER ☐ TABLE 1, 64E-6, FAC
SITE CONDITIONS: ☒ DRAINAGE STRUCTURES ☐ POOL ☐ PATIO / DECK ☐ PARKING
☐ SLOPING PROPERTY ☐
NATURE OF FAILURE: ☐ HYDRAULIC OVERLOAD ☐ SOILS ☐ MAINTENANCE ☒ SYSTEM DAMAGE
☒ DRAINAGE / RUN OFF ☐ ROOTS ☐ WATER TABLE ☐
FAILURE SYMPTOM: ☒ SEWAGE ON GROUND ☐ TANK ☐ D BOX/HEADER ☐ DRAINFIELD
☐ PLUMBING BACKUP ☐

REMARKS/ADDITIONAL CRITERIA _____

SUBMITTED BY: David Benoit TITLE/LICENSE ES-11
DH 4015, 08/09 (Obsoletes previous editions which may not be used)
Incorporated 64E-6.001, FAC

DATE: 10-15-20



STATE OF FLORIDA
DEPARTMENT OF HEALTH
ONSITE SEWAGE TREATMENT AND DISPOSAL SYSTEM
SITE EVALUATION AND SYSTEM SPECIFICATIONS

PERMIT #. 10-579-20

South 1/2

APPLICANT: Alachua Co Housing Authority AGENT: Beltz

LOT: _____ BLOCK: _____ SUBDIVISION: _____

PROPERTY ID #: 650801 004 [Section/Township/Parcel No. or Tax ID Number]

TO BE COMPLETED BY ENGINEER, HEALTH DEPARTMENT EMPLOYEE, OR OTHER QUALIFIED PERSON. ENGINEERS MUST PROVIDE REGISTRATION NUMBER AND SIGN AND SEAL EACH PAGE OF SUBMITTAL. COMPLETE ALL ITEMS.

PROPERTY SIZE CONFORMS TO SITE PLAN: ☐ YES ☐ NO NET USABLE AREA AVAILABLE: _____ ACRES
TOTAL ESTIMATED SEWAGE FLOW: 2500 GALLONS PER DAY [RESIDENCES-TABLE 1/OTHER-TABLE 2]
AUTHORIZED SEWAGE FLOW: _____ GALLONS PER DAY [1500 GPD/ACRE OR 2500 GPD/ACRE]
UNOBSTRUCTED AREA AVAILABLE: 600 SQFT UNOBSTRUCTED AREA REQUIRED: 375 SQFT

BENCHMARK/REFERENCE POINT LOCATION: main w ribbon top of threshold back door
ELEVATION OF PROPOSED SYSTEM SITE IS 6 [INCHES/FT] [ABOVE/BELOW] BENCHMARK/REFERENCE POINT

THE MINIMUM SETBACK WHICH CAN BE MAINTAINED FROM THE PROPOSED SYSTEM TO THE FOLLOWING FEATURES
SURFACE WATER: _____ FT DITCHES/SWALES: _____ FT NORMALLY WET? ☐ YES ☐ NO
WELLS: PUBLIC: _____ FT LIMITED USE: _____ FT PRIVATE: _____ FT NON-POTABLE: _____ FT
BUILDING FOUNDATIONS: 5 FT PROPERTY LINES: 5 FT POTABLE WATER LINES: 30 FT

SITE SUBJECT TO FREQUENT FLOODING: ☐ YES ☒ NO 10 YEAR FLOODING? ☐ YES ☒ NO
10 YEAR FLOOD ELEVATION FOR SITE: NA FT MSL/NGVD SITE ELEVATION: NA FT MSL/NGVD

SOIL PROFILE INFORMATION SITE 1 - 6

MUNSELL #/COLOR	TEXTURE	DEPTH
10yr 5/2	FS	0 TO 10
7/4	FS	10 TO 52
7.5yr 6/10	SL	52 TO 72
		TO
		TO
		TO
		TO
		TO
		TO
USDA SOIL SERIES: <u>Arredondo</u>		

SOIL PROFILE INFORMATION SITE 2 - 19

MUNSELL #/COLOR	TEXTURE	DEPTH
10yr 5/2	FS	0 TO 10
6/4	FS	10 TO 48
6/10 5/14	FS SL	48 TO 52
* 6/2	CMNDST RF	52 TO 72
		TO
		TO
		TO
		TO
		TO
USDA SOIL SERIES: <u>Bonnieville</u>		

OBSERVED WATER TABLE: 60 INCHES [ABOVE / BELOW] EXISTING GRADE. TYPE: PERCHED / APPARENT]
ESTIMATED WET SEASON WATER TABLE ELEVATION: 59 INCHES [ABOVE / BELOW] EXISTING GRADE
HIGH WATER TABLE VEGETATION: ☐ YES ☒ NO MOTTLING: ☒ YES ☐ NO DEPTH: 56 INCHES

SOIL TEXTURE/LOADING RATE FOR SYSTEM SIZING: Table II DEPTH OF EXCAVATION: * INCHES
DRAINFIELD CONFIGURATION: ☒ TRENCH ☒ BED ☐ OTHER (SPECIFY)
REMARKS/ADDITIONAL CRITERIA: remove existing dr install at or above existing
S. 1/2 of split system

SITE EVALUATED BY: Jared Bennett DATE: 10-15-20



STATE OF FLORIDA
DEPARTMENT OF HEALTH
ONSITE SEWAGE TREATMENT AND DISPOSAL
SYSTEM

16-579-26
PERMIT #: **01-SA-2184049**
APPLICATION #: **AP1583228**
DATE PAID: _____
FEE PAID: _____
RECEIPT #: _____
DOCUMENT #: **PR1454612**

CONSTRUCTION PERMIT FOR: OSTDS Repair
APPLICANT: (Alachua County Housing Authority (South System))
PROPERTY ADDRESS: 17056 SW 141st Pl Archer, FL 32618
LOT: 4 BLOCK: nr SUBDIVISION: Thistle Hills West
PROPERTY ID #: 05081-004-000 [SECTION, TOWNSHIP, RANGE, PARCEL NUMBER]
[OR TAX ID NUMBER]

SYSTEM MUST BE CONSTRUCTED IN ACCORDANCE WITH SPECIFICATIONS AND STANDARDS OF SECTION 381.0065, F.S., AND CHAPTER 64E-6, F.A.C. DEPARTMENT APPROVAL OF SYSTEM DOES NOT GUARANTEE SATISFACTORY PERFORMANCE FOR ANY SPECIFIC PERIOD OF TIME. ANY CHANGE IN MATERIAL FACTS, WHICH SERVED AS A BASIS FOR ISSUANCE OF THIS PERMIT, REQUIRE THE APPLICANT TO MODIFY THE PERMIT APPLICATION. SUCH MODIFICATIONS MAY RESULT IN THIS PERMIT BEING MADE NULL AND VOID. ISSUANCE OF THIS PERMIT DOES NOT EXEMPT THE APPLICANT FROM COMPLIANCE WITH OTHER FEDERAL, STATE, OR LOCAL PERMITTING REQUIRED FOR DEVELOPMENT OF THIS PROPERTY.

SYSTEM DESIGN AND SPECIFICATIONS

T [750] GALLONS / GPD existing septic tank CAPACITY
A [0] GALLONS / GPD CAPACITY
N [0] GALLONS GREASE INTERCEPTOR CAPACITY [MAXIMUM CAPACITY SINGLE TANK:1250 GALLONS]
K [] GALLONS DOSING TANK CAPACITY [] GALLONS @ [] DOSES PER 24 HRS #Pumps []
D [250] SQUARE FEET replacement for 1/2 SYSTEM
R [0] SQUARE FEET SYSTEM
A TYPE SYSTEM: [x] STANDARD [] FILLED [] MOUND []
I CONFIGURATION: [] TRENCH [x] BED []
N
F LOCATION OF BENCHMARK: top of threshold back door
I ELEVATION OF PROPOSED SYSTEM SITE [6.00] [INCHES] FT [] ABOVE [BELOW] BENCHMARK/REFERENCE POINT
E BOTTOM OF DRAINFIELD TO BE [36.00] [INCHES] FT [] ABOVE [BELOW] BENCHMARK/REFERENCE POINT
L
D FILL REQUIRED: [0.00] INCHES EXCAVATION REQUIRED: [] INCHES

permit based on replacing the existing amount of field as a bed on a split system repair with a maximum occupancy of 8 persons (2 per bedroom), ~~for a total estimated flow of 400 gpd.~~ remove any old drain field and unsuitable soil under and around the new installation dispose of properly replace with suitable fill. Install a new drainfield to achieve Drainfield size requirement.
ACAD encourages 400 ft² bed for full repair sizing, or a P.E. Plan split @ .8 trench or .6 bed for new sizing standards.

SPECIFICATIONS BY: Fred L Bennett TITLE: Environmental Specialist II
APPROVED BY: Fred L Bennett TITLE: Environmental Specialist II Alachua CHD
DATE ISSUED: 10/21/2020 EXPIRATION DATE: 01/19/2021
DH 4016, 08/09 (Obsoletes all previous editions which may not be used)
Incorporated: 64E-6.003, FAC

АСТА



Ana M. Viamonte Ros, M.D., M.P.H.
State Surgeon General

Acknowledgement & Check List

Nearest intersection within ¼ mile

This intersection is within ¼ mile [☒] yes [☐] no If no, it is [] miles from my property.

Owner Agreement for Representation

Date _____

Acknowledgement

Date



Parcel Summary

Parcel ID 05081-004-000
Prop ID 25474
Location Address 17054 SW 141ST PL
 ARCHER, FL 32618
Neighborhood/Area CITY OF ARCHER (216216.01)
Subdivision THISTLE HILLS WEST
Brief Legal Description* THISTLE HILLS WEST PB H-28 LOT 4 OR 804/350
 (Note: *The Description above is not to be used on legal documents.)
Property Use Code CTY INC NONMUNI (08600)
Sec/Twp/Rng 17-11-18
Tax District ARCHER (District 1007)
MillageRate 26.7223
Acreage 0.170
Homestead N

[View Map](#)

Owner Information

ALACHUA COUNTY HOUSING, AUTHOR
 701 NE 1ST ST
 GAINESVILLE, FL 32601

Valuation

	2019 Certified Values	2018 Certified Values	2017 Certified Values	2016 Certified Values	2015 Certified Values
Improvement Value	\$55,573	\$47,200	\$48,100	\$44,900	\$45,800
Land Value	\$8,000	\$8,000	\$8,000	\$8,000	\$8,000
Land Agricultural Value	\$0	\$0	\$0	\$0	\$0
Agricultural (Market) Value	\$0	\$0	\$0	\$0	\$0
Just (Market) Value	\$63,573	\$55,200	\$56,100	\$52,900	\$53,800
Assessed Value	\$60,720	\$55,200	\$56,100	\$52,900	\$53,800
Exempt Value	\$60,720	\$55,200	\$56,100	\$52,900	\$0
Taxable Value	\$0	\$0	\$0	\$0	\$53,800
Maximum Save Our Homes Portability	\$2,853	\$0	\$0	\$0	\$0

Just (Market) Value description - This is the value established by the Property Appraiser for ad valorem purposes. This value does not represent anticipated selling price.

TRIM Notice

[2020 TRIM Notice \(PDF\)](#)

Land Information

Land Use	Land Use Desc	Acres	Square Feet	Frontage	Depth
0100	SFR	0.00	1	0	0

Building Information

Type	SINGLE FAMILY	Heat	03-GAS
Total Area	1,305	HC&V	02-CONVECTION
Heated Area	1,225	HVAC	01-NONE
Exterior Walls	15-CONCRETE BLOCK	Bathrooms	1.5-Baths
Interior Walls	05-DRYWALL	Bedrooms	4-4 BEDROOMS
Roofing	03-ASPHALT	Total Rooms	
Roof Type	03-GABLE/HIP	Stories	1.0
Frame		Actual Year Built	1900
Floor Cover	07-CORK TILE	Effective Year Built	1972


Type	SOH MISC	Heat	
Total Area	250	HC&V	
Heated Area		HVAC	
Exterior Walls		Bathrooms	
Interior Walls		Bedrooms	
Roofing		Total Rooms	
Roof Type		Stories	1.0
Frame		Actual Year Built	1967
Floor Cover		Effective Year Built	1967

Sub Area


Type	Description	Sq. Footage	Year	Quality	Imprv Use	Imprv Use Descr
BAS	BASE AREA	1,225	1972	3	0100	SINGLE FAMILY
FOP	FINISHED OPEN PORCH	80	1972	3	0100	SINGLE FAMILY

Type	Description	Sq. Footage	Year	Quality	Imprv Use	Imprv Use Descr
3800	DRIVE/WALK	250	1967		C1	COMM

Sketches



Map Download



No data available for the following modules: Extra Features, Sales, Photos.

This web application and the data herein is prepared for the inventory of real property found within Alachua County and is compiled from tax and deeds plans, and other public records and data. Users of this web application and the data herein are hereby notified that the aforementioned public primary information sources should be consulted for verification of the information. Alachua County Property Appraiser's Office assumes no legal responsibility for the information contained herein.

[User Privacy Policy](#)
[GDPR Privacy Notice](#)

Last Data Upload: 10/6/2020, 11:35:41 PM

Developed by
 Schneider
 GEOSPATIAL

Version 2.3.88

IN THE SE 1/4 OF SECTION 17 - T 11 S - R 10 E
CITY OF ARCHER, ALACHUA COUNTY, FLORIDA

PLAY BOOK H



1. The first step in the process is to identify the problem. This involves gathering information about the situation and the people involved.

Handwritten signature: *[Illegible]*

1. The first step in the process is to identify the problem or issue that needs to be addressed. This involves gathering information and understanding the context of the problem.

DATE 6-1-72 BY SA [redacted]

1. address letter "Mr. Paul C. ... address ... This
2.
3.
4.
5.
6.
7.
8.
9.
10.
11.
12.
13.
14.
15.
16.
17.
18.
19.
20.
21.
22.
23.
24.
25.
26.
27.
28.
29.
30.
31.
32.
33.
34.
35.
36.
37.
38.
39.
40.
41.
42.
43.
44.
45.
46.
47.
48.
49.
50.
51.
52.
53.
54.
55.
56.
57.
58.
59.
60.
61.
62.
63.
64.
65.
66.
67.
68.
69.
70.
71.
72.
73.
74.
75.
76.
77.
78.
79.
80.
81.
82.
83.
84.
85.
86.
87.
88.
89.
90.
91.
92.
93.
94.
95.
96.
97.
98.
99.
100.
101.
102.
103.
104.
105.
106.
107.
108.
109.
110.
111.
112.
113.
114.
115.
116.
117.
118.
119.
120.
121.
122.
123.
124.
125.
126.
127.
128.
129.
130.
131.
132.
133.
134.
135.
136.
137.
138.
139.
140.
141.
142.
143.
144.
145.
146.
147.
148.
149.
150.
151.
152.
153.
154.
155.
156.
157.
158.
159.
160.
161.
162.
163.
164.
165.
166.
167.
168.
169.
170.
171.
172.
173.
174.
175.
176.
177.
178.
179.
180.
181.
182.
183.
184.
185.
186.
187.
188.
189.
190.
191.
192.
193.
194.
195.
196.
197.
198.
199.
200.
201.
202.
203.
204.
205.
206.
207.
208.
209.
210.
211.
212.
213.
214.
215.
216.
217.
218.
219.
220.
221.
222.
223.
224.
225.
226.
227.
228.
229.
230.
231.
232.
233.
234.
235.
236.
237.
238.
239.
240.
241.
242.
243.
244.
245.
246.
247.
248.
249.
250.
251.
252.
253.
254.
255.
256.
257.
258.
259.
260.
261.
262.
263.
264.
265.
266.
267.
268.
269.
270.
271.
272.
273.
274.
275.
276.
277.
278.
279.
280.
281.
282.
283.
284.
285.
286.
287.
288.
289.
290.
291.
292.
293.
294.
295.
296.
297.
298.
299.
300.
301.
302.
303.
304.
305.
306.
307.
308.
309.
310.
311.
312.
313.
314.
315.
316.
317.
318.
319.
320.
321.
322.
323.
324.
325.
326.
327.
328.
329.
330.
331.
332.
333.
334.
335.
336.
337.
338.
339.
340.
341.
342.
343.
344.
345.
346.
347.
348.
349.
350.
351.
352.
353.
354.
355.
356.
357.
358.
359.
360.
361.
362.
363.
364.
365.
366.
367.
368.
369.
370.
371.
372.
373.
374.
375.
376.
377.
378.
379.
380.
381.
382.
383.
384.
385.
386.
387.
388.
389.
390.
391.
392.
393.
394.
395.
396.
397.
398.
399.
400.
401.
402.
403.
404.
405.
406.
407.
408.
409.
410.
411.
412.
413.
414.
415.
416.
417.
418.
419.
420.
421.
422.
423.
424.
425.
426.
427.
428.
429.
430.
431.
432.
433.
434.
435.
436.
437.
438.
439.
440.
441.
442.
443.
444.
445.
446.
447.
448.
449.
450.
451.
452.
453.
454.
455.
456.
457.
458.
459.
460.
461.
462.
463.
464.
465.
466. ...

1. 11. 11.

Wm. W. Barker - John ¹⁹¹⁴
 Wm. W. Barker - John ¹⁹¹⁴
 Wm. W. Barker - John ¹⁹¹⁴

I



Alachua County Health Department
224 SE 24th St Gainesville, FL 32641

PAYING ON: # 01-SA-2184049 BILL DOC #: 1-BID-5048985 CONSTRUCTION APPLICATION #: AP1583228
RECEIVED FROM: Beltz Liquid Waste Management, Inc. AMOUNT PAID: \$ 300.00
PAYMENT FORM: CREDIT CARD 9789 Visa PAYMENT DATE: 10/08/2020

MAIL TO: (Alachua County Housing Authority (South System))

FACILITY NAME : _____

PROPERTY LOCATION:

17056 SW 141st Pl
Archer, FL 32618

Lot: 4 Block: _____

Property ID: 05081-004-000

EXPLANATION or DESCRIPTION:	QUANTITY	FEE
130 - OSTDS Construction System Inspection Training Cent	1	\$ 5.00
124 - OSTDS Construction Repair or Mod Site Evaluation	1	\$ 115.00
127 - OSTDS Construction System Inspection	1	\$ 75.00
129 - OSTDS Construction Permit (Repair)	1	\$ 55.00
131 - OSTDS Construction Application & Existing System E	1	\$ 50.00

RECEIVED BY: CribbsTL2

AUDIT CONTROL NO. 1-PID-4747617

Note: repair permit 10-579-20; Beltz emailed app



STATE OF FLORIDA
DEPARTMENT OF HEALTH AND REHABILITATIVE SERVICES
ONSITE SEWAGE DISPOSAL SYSTEM CONSTRUCTION AND INSTALLATION PERMIT

Authority: Chapter 381, FS
Chapter 10D-6, FAC

Applicant AL. CO. HOUSING AUTHORITY

759
Permit Number 12-757-91R

PART I - SYSTEM CONSTRUCTION SPECIFICATIONS AND CONSTRUCTION APPROVAL

Treatment Tank		Minimum Drains Trench	OR	Minimum Absorption
Septic tank or aerobic unit	Grease interceptor	Size		Bed Size
<u>1050</u> OR <u>EXISTING IF FUNCTIONAL</u> gallons	_____ gallons	<u>200</u> Square Feet		<u>250</u> Square Feet
Septic tank or aerobic unit _____ gallons	Dosing tank _____ gallons	_____ Square Feet		_____ Square Feet
Graywater tank _____ gallons		_____ Square Feet		_____ Square Feet
Laundry waste tank _____ gallons		_____ Square Feet		_____ Square Feet

Other Requirements:

- (a) Installation must be in accord with requirements of chapter 10D-6, FAC.
(b) A system construction permit is valid for a period of one calendar year from date of issue.
(c) Final installation inspection and approval is required before the system is covered.
(d) Invert of stub-out for D-BOX to be 12-24" BELOW NATURAL GRADE benchmark.
Invert of stub-out for _____ to be OR benchmark.
Invert of stub-out for _____ to be 14-26" BELOW benchmark.
Invert of stub-out for _____ to be _____ benchmark.

(e) Fill quality and quantity:

* DUAL septic tank system - split flow / drainfield
200 ft² - will install in bed - absorption bed size
to be 250 ft². (IS) As per Donald #1 - Sept 12/20/91

(f) Other: E/HWT 60"
600 GPD MAX DF CAP
2.0 G/FT²/D

System design and specifications by: _____ Title _____

Construction authorized by: Dennis Charky Date 12/11/91

ALACHUA County Public Health Unit

Note: Completed copies of this form will be provided to the applicant, installer and the building department.



STATE OF FLORIDA
DEPARTMENT OF HEALTH AND REHABILITATIVE SERVICES
APPLICATION FOR ONSITE SEWAGE DISPOSAL SYSTEM CONSTRUCTION PERMIT

Authority: Chapter 381, FS
Chapter 10D-6, FAC

Date of Application

12/9/91

Permit Application Number

12-759-91R

PART I - APPLICATION

Name of Owner Alachua County Housing Telephone Number 372-2549

Mailing Address of Owner 636 N.E. 1st. Gainesville, FL. 32601

Owner's Agent Alachua County Housing Builder _____

Agent's Mailing Address _____ Telephone No. _____

Property Street Address Lot #4 140 Thistle Hills West, Archer

Lot No. 4 Block No. 140 Subdivision THW Date Subdivided 1971

NOTE: IF NOT IN A SUBDIVISION ATTACH A METES AND BOUNDS DESCRIPTION

This Application is for: New System _____ Repair ☒ Existing System _____

Type of
Establishment

Sewage Flow
(Gallons per day)

Sewage Flow
Based On

12/10/91 NO FLAG, ADDRESS? DO

House built about

30 years ago.

TOTAL FLOW = 14,000 ft² .32 ACRE

Type of
Residential

No. Bedrooms
(each dwelling unit)

Heated or Cooled Area
(each dwelling unit)

No. Dwelling
Units

Sewage Flow
(Gallons per day)

SD

4 Bedroom

1625 ft²

1

450

Exact Directions to Property Hwy 24 to Archer, left at light, Right
at Fire Station to Stop sign left 1/4 - 1/2 mile on
Right. 24/5

AUDIT CONTROL NO 232877

Applicant's Signature

John H. H. H.

no charge

County

Cribbs, Tina L

From: Sunshine 811 Exactix <no-reply@exactix.sunshine811.com>
Sent: Wednesday, October 7, 2020 5:00 PM
To: Cribbs, Tina L
Subject: SSOCOF CONFRM 2020/10/07 #00000 281007305-000 NORM NEW

CONFRM 00000 CALL SUNSHINE 10/07/20 16:59:32ET 281007305-000 STREET Ticket : 281007305 Rev:000 Taken: 10/07/20 16:57ET

State: FL Cnty: ALACHUA GeoPlace: ARCHER
CallerPlace: ARCHER
Subdivision: THISTLE HILLS WEST Lot: 4

*Repair
10/12*

Address : 17056
Street : SW 141ST PL
Cross 1 : GIBSON AVE
Within 1/4 mile: Y

Locat: THE ENTIRE PROPERTY DUE TO THERE ARE TWO REPAIRS GOING ON AT THIS LOT

Remarks : *** LOOKUP BY ADDRESS ***

Grids : 2931C8231C

Work date: 10/09/20 Time: 23:59ET Hrs notc: 059 Category: 3 Duration: 01 HR Due Date : 10/09/20 Time: 23:59ET Exp Date : 11/06/20 Time: 23:59ET Work type: SEPTIC Boring: N White-lined: N
Ug/Oh/Both: U Machinery: N Depth: 6 FT Permits: Y 10-578-20 10-579-20 Done for : ALACHUA COUNTY HOUSING AUTHORITY

Company : ALACHUA COUNTY HEALTH DEPARTMENT Type: CONT Co addr : 224 SE 24TH ST Co addr2: DEPT 30EH
City : GAINESVILLE State: FL Zip: 32641
Caller : TINA CRIBBS Phone: 352-334-7930
BestTime: MON-FRI 8-5
Fax : 352-334-7935
Email : TINA.CRIBBS@FLHEALTH.GOV

Submitted: 10/07/20 16:57ET Oper: TIN Chan: WEB Mbrs : CLAY05 COA881 GN1349 PE1371 SBF09



12/30 2:55

Ellen
STATE OF FLORIDA
DEPARTMENT OF HEALTH AND REHABILITATIVE SERVICES

45 @ 300 12/31

ON-SITE SEWAGE DISPOSAL SYSTEM CONSTRUCTION AND INSTALLATION PERMIT

Applicant Alachua County Housing

Permit Number 12-759-91R

PART II - SYSTEM INSTALLATION INSPECTION AND FINAL INSTALLATION APPROVAL

Installer Florida Septic Tank Manufacturer _____

Proper tank legend: Yes _____ No EXISTING Tank material _____ Tank level: Yes _____ No _____

Tanks watertight: Yes _____ No _____ Tank size: _____ gallons _____ gallons _____ gallons

Proper tank outlet device: Yes _____ No _____ Manhole or marker to grade: Yes _____ No _____

Drainfield Trench

Absorption Bed

Length	Width	Length	Width	Length	Width
_____ feet	_____ feet	_____ feet	_____ feet	Length <u>28</u> feet x <u>9</u> feet <u>250</u> ft ²	
_____ feet	_____ feet	_____ feet	_____ feet	Length _____ feet x _____ feet = _____ ft ²	
_____ feet	_____ feet	_____ feet	_____ feet	Proper No. drainlines: Yes <u>✓</u> No _____	
				Proper pipe separation: Yes <u>✓</u> No _____	
Total = _____ ft ²		Total = _____ ft ²		Distribution box level: Yes <u>✓</u> No _____	

Systems located as permitted: Yes ✓ No _____

Systems including plumbing stub-outs installed at proper elevation: Yes ✓ No _____

Average depth to drainpipe invert from finished grade: 13 inches Maximum depth: 16 inches

Average depth of drainfield gravel: 12 inches Minimum depth of gravel: 12 inches

Proper gravel size: Yes ✓ No _____ Gravel is suitable quality: Yes ✓ No _____

Backfill or fill material as required: (Quality) Yes ✓ No _____ (Quantity) Yes ✓ No _____

Other findings: _____

Inspected by: Dennis Chabz Date 12/31/91

PART III - FINAL INSTALLATION APPROVAL

Date 12/31/91 Approved by: Dennis Chabz ALACHUA
COUNTY PUBLIC HEALTH UNIT

AN APPROVED INSTALLATION DOES NOT GUARANTEE PERFORMANCE

Note: Completed copies of this form will be provided to the applicant, installer and the building department.



**STATE OF FLORIDA
DEPARTMENT OF HEALTH AND REHABILITATIVE SERVICES
APPLICATION FOR ONSITE SEWAGE DISPOSAL SYSTEM CONSTRUCTION PERMIT**

Applicant AL CO HOUSING AUTHORITY Permit Application Number 12-75991R

PART III - SITE EVALUATION INFORMATION

- Lot size appears to be as indicated on site plan: Yes ☒ No ☐
 - Anticipated sewage flow from Part I 450 GPD Authorized sewage flow 800 GPD
 - Benchmark location PATIO SLAB IN SIDE OF HOUSE ~30' N FAS
 - Existing elevation (at time of site evaluation) of the proposed system site in relation to the benchmark is 2 inches above/below the benchmark.
 - Proposed system distance to: Surface water feet feet feet; Private potable wells feet feet feet; Community public wells feet feet; Other public wells feet feet; Non-potable wells feet feet;
 - Unobstructed area available for system installation 1000 ft² ft² ft²
 - Is lot subject to frequent flooding? Yes ☐ No ☒ 10 year flood? Yes ☐ No ☒
- If subject to a 10 year flood indicate: (a) the 10 year flood elevation in the area feet MSL
(b) property elevation at proposed system location feet MSL.

10/2 SOIL PROFILE - SAMPLE SITE 1 + 2 SAME

	COLOR	TEXTURE	DEPTH
5/2	GRAY BROWN	SAND	0" to 10"
6/4	LT YELLOW BROWN	SAND	10" to 40"
7/3	VP BROWN WHITE	SAND	40" to 72"
			" to "
			" to "
			" to "

SOIL PROFILE - SAMPLE SITE 2

	COLOR	TEXTURE	DEPTH
	JAME		0" to "
			" to "
			" to "
			" to "
			" to "
			" to "

USDA Soil Series Name (if Known) SIMILAR TO CANDLER USDA Soil Series Name (if Known)
USDA Soil texture classification on which drainfield size should be based SAND

Water table at time of evaluation
> 72 inches below/above existing grade

Estimated wet season water table 60 inches below/above existing grade

Type water table:
Perched ☐ Apparent ☒

Is mottling found in the soil? Yes ☒ No ☐
At what depth? 60 inches 100 inches

Are vegetative species indicative of high water table? Yes ☐ No ☒

For property with contiguous ditches:
Depth of ditches inches inches
Depth of water in ditches inches inches


Other findings:

Date of Site Evaluation 12/11/91

Evaluator's Signature *Dennis Chalky*
(Include seal if performed by P.E.)

Request for Permit For Repairs 12-04-91 140 THW PLAN FOR SEPTIC DRAIN FIELD REPLACEMENT

Approved 12/11/91



Plan is to install new drain field in place of existing or make as septic contractor sees fit

4 Bedroom house

2 Bathroom

140 Thistle Hills west 120

Archer, Elm 52618

Lot #4, Alabama County, Housing Authority

Dorothy Barber - Tenant

140 THW STREET

12-139-918

10/22
9:57



Darla
Beltz

STATE OF FLORIDA
DEPARTMENT OF HEALTH
ONSITE SEWAGE TREATMENT AND DISPOSAL SYSTEM
CONSTRUCTION INSPECTION AND FINAL APPROVAL

PERMIT NO. 10579-20
DATE PAID: 10/8/20
FEE PAID: 300.00
RECEIPT #: 46048985
AP1583228

APPLICANT: Alachua County Housing Authority (South)

AGENT:

PROPERTY ADDRESS: 17056 SW 141st Place Archer 71 32618

LOT: BLOCK: SUBDIVISION: PROPERTY ID #: DS081-004-000

CHECKED [X] ITEMS ARE NOT IN COMPLIANCE WITH STATUTE OR RULE AND MUST BE CORRECTED.

TANK INSTALLATION

- [] [01] TANK SIZE [1] 750 [2] N
[] [02] TANK MATERIAL concrete
[] [03] OUTLET DEVICE
[] [04] MULTI-CHAMBERED [Y / N]
[] [05] OUTLET FILTER
[] [06] LEGEND unk
[] [07] WATERTIGHT
[] [08] LEVEL
[] [09] DEPTH TO LID

DRAINFIELD INSTALLATION

- [] [10] AREA [1] 270 [2] N SQFT
[] [11] DISTRIBUTION BOX HEADER ✓
[] [12] NUMBER OF DRAINLINES 2
[] [13] DRAINLINE SEPARATION
[] [14] DRAINLINE SLOPE
[] [15] DEPTH OF COVER
[] [16] ELEVATION [ABOVE (BELOW) BM 39]
[] [17] SYSTEM LOCATION
[] [18] DOSING PUMPS N
[] [19] AGGREGATE SIZE
[] [20] AGGREGATE EXCESSIVE FINES
[] [21] AGGREGATE DEPTH

FILL / EXCAVATION MATERIAL

- [] [22] FILL AMOUNT
[] [23] FILL TEXTURE
[] [24] EXCAVATION DEPTH
[] [25] AREA REPLACED
[] [26] REPLACEMENT MATERIAL

SETBACKS

- [] [27] SURFACE WATER
[] [28] DITCHES
[] [29] PRIVATE WELLS
[] [30] PUBLIC WELLS
[] [31] IRRIGATION WELLS
[] [32] POTABLE WATER LINES 30
[] [33] BUILDING FOUNDATION 5
[] [34] PROPERTY LINES 5
[] [35] OTHER

FILLED / MOUND SYSTEM

- [] [36] DRAINFIELD COVER
[] [37] SHOULDERS
[] [38] SLOPES
[] [39] STABILIZATION N

ADDITIONAL INFORMATION

- [] [40] UNOBSTRUCTED AREA
[] [41] STORMWATER RUNOFF
[] [42] ALARMS
[] [43] MAINTENANCE AGREEMENT
[] [44] BUILDING AREA
[] [45] LOCATION CONFORMS WITH SITE PLAN
[] [46] FINAL SITE GRADING
[] [47] CONTRACTOR Beltz
[] [48] OTHER ADS Septic stack 9

ABANDONMENT

- [] [49] TANK PUMPED N
[] [50] TANK CRUSHED & FILLED N

EXPLANATION OF VIOLATIONS / REMARKS:

[] held levy

CONSTRUCTION [APPROVED/DISAPPROVED]: Fred Bennett

FINAL SYSTEM [APPROVED/DISAPPROVED]: Fred Bennett

DH 4016, 08/09 (Obsoletes all previous editions which may not be used)
Incorporated: 64E-6.003, FAC

CHD DATE: 10-29-20

CHD DATE: 10-29-20

PERMIT NUMBER: Permit tracking number assigned by CHD.
 APPLICANT: Property owner's full name.
 AGENT: Property owner's legally authorized representative.
 MAILING ADDRESS: P.O. box or street mailing address for applicant or agent.
 LOT, BLOCK, SUBDIVISION: Lot, Block and Subdivision for lot or
 PROPERTY ID#: 27 character number for property. (property appraiser ID # or GIS location)

COUNTY HEALTH DEPARTMENT CHECKS [X] ITEMS NOT IN COMPLIANCE WITH CONSTRUCTION PERMIT AND STATUTE OR RULE. INFORMATION IS COMPLETED BY CHD ON FOLLOWING ITEMS:

TANK SIZE (gallons)
 TANK MATERIAL (concrete, fiberglass, etc)
 OUTLET FILTER (manufacturer, make, model)
 LEGEND (manufacturer code)
 DRAINFIELD AREA (square feet)
 DISTRIBUTION BOX / HEADER (check box)
 NUMBER OF DRAINLINES (number installed)
 SYSTEM ELEVATION (in relation to BM)
 DOSING PUMPS (number installed)
 SETBACKS (record actual setbacks in ft)
 SETBACKS OTHER (as required)
 STABILIZATION (date stabilized)
 CONTRACTOR (contractor installing system)
 ADDITIONAL INFORMATION (as required)
 ABANDONMENT TANK PUMPED (date)
 TANK CRUSHED AND FILLED (date)
 AS BUILT INSTALLATION SKETCH

EXPLANATION OF VIOLATIONS: Record item number, explanation of violation, and required corrective action.
 CONSTRUCTION APPROVAL: Circle approved or disapproved, CHD signature and date.
 FINAL APPROVAL: Circle approved or disapproved. CHD signature and date of approval.
 Final approval shall not be granted until the CHD has confirmed that building construction and lot grading are in substantial compliance with plans and specifications submitted with the permit application.

ELEVATION WORKSHEET		ELEVATION OF BENCHMARK OR REFERENCE POINT: _____			
[+] SHOT	_____	EXISTING GROUND	_____	TOP OF AGGREGATE	_____
H.I.	_____	H.I.	_____	H.I.	_____
ELEVATION	_____	[-] SHOT	_____	[-] SHOT	_____